



Pacific Standard Environmental, Inc.
2750 S Harbor Blvd
Ste A
Santa Ana CA 92704 US

DATE
2/20/2026

TERMS
As Agreed

EXPIRES
5/22/2026

ESTIMATE #
26022003MS

ESTIMATE

BILL TO

Carson Cogen
Carson Cogen
17171 S Central Ave
Carson CA 90746

SHIP TO

CONTACT

Albert Dietz
adietz@ches.biz

DESCRIPTION	QTY	RATE	AMOUNT
-------------	-----	------	--------

Carson Cogen - Inlet and Outlet Continuous Emissions Monitoring Systems
Equipment_Multi Point Probe_Shelter_26.02.20

The information contained in this document is classified as Pacific Standard Environmental, Inc. confidential. This proposal is for the express use of providing scope of supply and pricing for goods & services between Carson Cogen and Pacific Standard Environmental, Inc. Unauthorized distribution, or discussion of the information discussed in this presentation is prohibited.

PSE NOx/CO/O2 Outlet CEMS and NOx/O2 Inlet CEMS to meet SCAQMD and USEPA 40 CFR 60 Appendix B PS-2, PS-3, PS-4 and Appendix F Procedure 1

TBD PARTS

PSE System Hardware

- Two (2) PSE 8 LPM Sample Conditioning Panels
- One (1) Multi Point Sample Probe w/ Blowback (stack)
- One (1) Extractive Sample Probe w/ Blowback (Inlet)
- Two (2) Heated Sample Lines (Not to Exceed 250' total)
- Two (2) TAPI T200M NOx/O2 Analyzers
- One (2) TAPI T300 CO Analyzers
- One (1) Up to 10' x 10' Shelter with Redundant A/C
- One UPS with Extended Battery Backup
- One (1) 19" Rack for Rack Mounted Equipment
- Two (2) Toggle Panels for System Control
- Two (2) Flow Panel for System Control
- One (1) VIM DAHS PLC Programming
- One (1) Allen Bradley 5380 PLC
- One Yokogawa Paperless Chart Recorder (RECLAIM Requirement)
- One (1) Electrical Control and Termination Panel
- One (1) Set Daily Gas Regulators and Protocol Stations

1.00

Parts

Misc Hardware - This is a not to exceed price for miscellaneous hardware needed to complete installation/commissioning. This is a not to exceed price; hardware will be billed for per item.

1.00

PO - Engineering

PO - Engineering (110 hours)

110.00



Pacific Standard Environmental, Inc.
2750 S Harbor Blvd
Ste A
Santa Ana CA 92704 US

DATE
2/20/2026

TERMS
As Agreed

EXPIRES
5/22/2026

ESTIMATE #
26022003MS

ESTIMATE

PO - Integration

PO - Integration/Procurement/QA (140 hours)

140.00

PO - Project Mgmt

PO - Project Management (60 hours)

60.00

PO - Installation/Comm.

PO - Installation/Commissioning (120 hours, Two Techs one week and One Tech one week
(Includes travel time, mileage and expenses)

140.00

Subcontractor

DAHS On-Site Commissioning Support (4 days)

4.00

Shipping/Packing Cost, Pre-pay and Add - TBD

Terms: Net 30 Days

Billing Milestones:

50% Due upon award

20% Due upon drawing submittal

20% Due upon shipment

10% Due upon startup and commissioning NTE (Not to Exceed) 60 days after delivery

This quote is valid for 90 days

Commercial Notes: Drawing delivery is 8-12 weeks ARO (After Receipt of Order) and Equipment Delivery is 30 weeks after drawing submittal. Warranty is twelve (12) months from start-up or eighteen (18) months from shipment whichever occurs first. (analyzers have 2-year warranty on defective parts)

Technical Notes:

Customer to supply installation of utilities and operating calibration gases.

****Price does not include applicable taxes****

SUBTOTAL

TAX