## Appendix D10: Walnut Creek 500 MW Project 911 Bixby Dr., City of Industry

Environmental Topic	Impact(s)	Mitigation	Conclusion
Aesthetics (Visual Resources) Construction	<b>PROJECT-SPECIFIC:</b> Nighttime construction activities could make the facility visible to local residents. <b>CUMULATIVE:</b> The areas surrounding the project site are largely built out and consist of heavy and light industrial land uses compatible with the proposed project. Based on the visual resources analysis, staff concluded that construction of the proposed project would cause significant direct or cumulative visual impacts.	VIS -2: The project owner shall ensure that lighting for construction of the power plant is used in a manner that minimizes potential night lighting impacts, as follows: A. All lighting shall be of minimum necessary brightness consistent with worker safety and security; B. All fixed position lighting shall be shielded/hooded, and directed downward and toward the area to be illuminated to prevent direct illumination of the night sky and direct light trespass (direct light extending into public viewing areas); C. Wherever feasible and safe and not needed for security, lighting shall be kept off when not in use; and D. Complaints concerning adverse lighting impacts will be promptly addressed.	Mitigated to less than significant.
Aesthetics (Visual Resources) Operation	<ul> <li>PROJECT-SPECIFIC: The project's presence would change the visual character of the view somewhat. The addition of prominently visible stacks, transmission towers, and other mechanical equipment of the project would make the view seem more industrial in nature but there should be little change in the overall visual quality of the view, and the overall visual change would be moderately low.</li> <li>During the operational stage, the proposed power plant would require onsite nighttime lighting for safety and security purposes.</li> <li>CUMULATIVE: The areas surrounding the project site are largely built out and consist of heavy and light industrial land uses compatible with the proposed project. Based on the visual resources analysis, staff concluded that construction of the proposed project would cause significant direct or cumulative visual impacts.</li> </ul>	VIS – 1: The project owner shall color and finish the surfaces of all project structures and buildings visible to the public to ensure that they: (1) minimize visual intrusion and contrast by blending with the landscape; (2) minimize glare; and (3) comply with local design policies and ordinances. The transmission line conductors shall be non-specular and non-reflective, and the insulators shall be non-reflective and non-refractive. VIS-3: To the extent feasible, consistent with safety and security considerations and commercial availability, the project owner shall design and install all permanent exterior lighting such that a) obtrusive	Mitigated to less than significant.

Environmental Topic	Impact(s)	Mitigation	Conclusion
		light and glare from on-site light fixtures is minimized from public viewing areas ; b) lighting does not cause excessive reflected glare; c) direct lighting does not illuminate the nighttime sky; d) illumination of the project and its immediate vicinity is minimized, and e) the plan complies with local policies and ordinances.	
Agricultural Resources - Construction	<b>PROJECT-SPECIFIC:</b> None identified in the document. <b>CUMULATIVE:</b> None identified in the document.	None identified in the document.	None identified in the document.
Agricultural Resources - Operation	<ul> <li>PROJECT-SPECIFIC: there are no areas used for agricultural production within a one-mile radius of the project site. The soils in the area are considered unsuitable for commercial crop production because of the industrial, commercial, and residential development in the area. The project site and surrounding areas are designated as "Urban and Built-Up Land" by the California Department of Conservation, and as such, are not designated as important farmland. In addition, the project site is not located in an area that has a Williamson Act contract. Implementation of the project would not result in the conversion of Prime Farmland, Unique Farmland, or Farmland of Statewide Importance to nonagricultural use. In addition, project implementation would not bring about any other changes in the environment that could result in the conversion of farmland to nonagricultural use.</li> <li>CUMULATIVE: No areas in the vicinity of the proposed site are used for agricultural production. The soils in this area have been developed for industrial, commercial, or residential uses and are unsuitable for commercial crop production. Therefore, the project would not by itself or cumulatively adversely affect lands designated Prime Farmland, Farmland of Statewide and Local Importance, or Unique Farmlands.</li> </ul>	None identified in the document.	Less than significant.
Air Quality (and Public Health) - Construction	<b>PROJECT-SPECIFIC</b> : NOx emissions during the first phase of project site activity, mostly due to earth moving, grading activities, large equipment operations, underground utility installation, and as building erection exceed the SCAQMD's recommended significance threshold. The project's construction emissions were modeled and the modeling demonstrated that project construction emissions will not cause a new violation of the NO2, CO and SO2 ambient air quality standards and, thus,	AQ-SC1 Air Quality Construction Mitigation Manager (AQCMM): The project owner shall designate and retain an on-site AQCMM who shall be responsible for directing and documenting compliance with conditions AQ-SC3, AQ-SC4 and AQ-	Mitigated to less than significant.

Environmental Topic	Impact(s)	Mitigation	Conclusion
	<ul> <li>those impacts are not considered significant. The modeling assessment indicates the project construction has the potential to contribute significantly to violations of the state 24-hour and annual PM10 AAQS. Therefore, PM10/PM2.5 emission impacts were concluded to be significant if left unmitigated, in the vicinity of the proposed project, and more local than regional in nature.</li> <li>The maximum theoretical cancer risk from such diesel exhaust was calculated by the applicant as 0.38 in a million at the maximum impact location at the project fence line. Staff considers the recommended control measures specified in Air Quality Condition of Certification (AQ-SC3) as adequate to minimize the cancer risk during the relatively short (12-month) construction period.</li> <li>CUMULATIVE: None identified in the document</li> </ul>	SC5 for the entire project site and linear facility construction. The on-site AQCMM may delegate responsibilities to one or more AQCMM Delegates. The AQCMM and AQCMM Delegates shall have full access to all areas of construction on the project site and linear facilities, and shall have the authority to stop any or all construction activities as warranted by applicable construction mitigation conditions. The AQCMM and AQCMM Delegates may have other responsibilities in addition to those described in this condition. The AQCMM shall not be terminated without written consent of the CPM. AQ-SC2 Air Quality Construction Mitigation Plan (AQCMP): The project owner shall provide an AQCMP, for approval, which details the steps that will be taken, and the reporting requirements necessary, to ensure compliance with conditions AQ-SC3, AQ-SC4 and AQ- SC5. AQ-SC3 Construction Fugitive Dust Control: The AQCMM shall submit documentation to the CPM in each Monthly Compliance Report (MCR) that demonstrates compliance with the following mitigation measures for the purposes of preventing all fugitive dust plumes from leaving the project site and linear facility routes. Any deviation from the following mitigation measures shall require prior CPM notification and approval. a) All unpaved roads and disturbed	
		shall require prior CPM notification and approval.	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		construction sites shall be watered as	
		frequently as necessary to comply with the dust mitigation objectives of AQ-	
		SC4. The frequency of watering may	
		be reduced or eliminated during periods	
		of precipitation.	
		b) No vehicle shall exceed 10 miles per	
		hour within the construction site. c)	
		The construction site entrances shall be	
		posted with visible speed limit signs.	
		d) All construction equipment vehicle	
		tires shall be inspected and washed as	
		necessary to be cleaned free of dirt	
		prior to entering paved roadways. e) Gravel ramps of at least 20 feet in	
		length must be provided at the tire	
		washing/cleaning station.	
		f) All unpaved exits from the	
		construction site shall be graveled or	
		treated to prevent track-out to public	
		roadways.	
		g) All construction vehicles shall enter	
		the construction site through the treated	
		entrance roadways, unless an	
		alternative route has been submitted to and approved by the CPM.	
		h) Construction areas adjacent to any	
		paved roadway shall be provided with	
		sandbags or other measures as specified	
		in the Storm Water Pollution	
		Prevention Plan (SWPPP) to prevent	
		run-off to roadways.	
		i) All paved roads within the	
		construction site shall be swept at least	
		twice daily (or less during periods of	
		precipitation) on days when	
		construction activity occurs to prevent the accumulation of dirt and debris.	
		j) At least the first 500 feet of any	
		j) At least the first 500 feet of ally	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		public roadway exiting from the	
		construction site shall be swept at least	
		twice daily (or less during periods of	
		precipitation) on days when	
		construction activity occurs or on any other day when dirt or runoff from the	
		construction site is visible on the public	
		roadways.	
		k) All soil storage piles and disturbed	
		areas that remain inactive for longer	
		than 10 days shall be covered, or shall	
		be treated with appropriate dust	
		suppressant compounds.	
		l) All vehicles that are used to transport	
		solid bulk material on public roadways	
		and that have the potential to cause	
		visible emissions shall be provided	
		with a cover, or the materials shall be	
		sufficiently wetted and loaded onto the	
		trucks in a manner to provide at least two feet of freeboard. m) Wind erosion	
		control techniques (such as windbreaks,	
		water, chemical dust suppressants,	
		and/or vegetation) shall be used on all	
		construction areas that may be	
		disturbed. Any windbreaks installed to	
		comply with this condition shall remain	
		in pl	
		AQ-SC4 Dust Plume Response	
		Requirement: The AQCMM or an	
		AQCMM Delegate shall monitor all	
		construction activities for visible dust	
		plumes. Observations of visible dust	
		plumes that have the potential to be transported $(1)$ off the project site or $(2)$	
		transported (1) off the project site or (2) 200 feet beyond the centerline of the	
		construction of linear facilities or (3)	
		within 100 feet upwind of any regularly	
		occupied structures not owned by the	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		project owner indicate that existing	
		mitigation measures are not resulting in	
		effective mitigation. The AQCMM or	
		Delegate shall implement the following procedures for additional mitigation	
		measures in the event that such visible	
		dust plumes are observed: Step 1: The	
		AQCMM or Delegate shall direct more	
		intensive application of the existing	
		mitigation methods within 15 minutes	
		of making such a determination. Step	
		2: The AQCMM or Delegate shall	
		direct implementation of additional	
		methods of dust suppression if Step 1	
		specified above fails to result in	
		adequate mitigation within 30 minutes of the original determination. Step 3:	
		The AQCMM or Delegate shall direct a	
		temporary shutdown of the activity	
		causing the emissions if Step 2	
		specified above fails to result in	
		effective mitigation within one hour of	
		the original determination. The activity	
		shall not restart until the AQCMM or	
		Delegate is satisfied that appropriate	
		additional mitigation or other site	
		conditions have changed so that visual	
		dust plumes will not result upon restarting the shutdown source. The	
		owner/operator may appeal to the CPM	
		any directive from the AQCMM or	
		Delegate to shut down an activity,	
		provided that the shutdown shall go	
		into effect within one hour of the	
		original determination, unless overruled	
		by the CPM before that time.	
		AQ-SC5 Diesel-Fueled Engines	
		Control: The AQCMM shall submit to	
		the CPM, in the MCR, a construction	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		mitigation report that demonstrates	
		compliance with the following	
		mitigation measures for the purposes of controlling diesel construction-related	
		emissions. Any deviation from the	
		following mitigation	
		measures shall require prior CPM	
		notification and approval. a) All diesel-	
		fueled engines used in the construction	
		of the facility shall be fueled only with	
		ultra-low sulfur diesel, which contains	
		no more than 15 ppm sulfur. b) All	
		diesel-fueled engines used in the	
		construction of the facility shall have	
		clearly visible tags issued by the on-site	
		AQCMM showing that the engine	
		meets the conditions set forth herein. c) All construction diesel engines that	
		have a rating of 100 hp or more, shall	
		meet, at a minimum, the Tier 2	
		California Emission Standards for Off-	
		Road Compression-Ignition Engines as	
		specified in California Code of	
		Regulations, Title 13, section	
		2423(b)(1) unless certified by the on-	
		site AQCMM that such engine is not	
		available for a particular item of	
		equipment. In the event a Tier 2 engine	
		is not available for any off-road engine	
		larger than 100 hp, that engine shall be	
		equipped with a Tier 1 engine. In the	
		event a Tier 1 engine is not available	
		for any off-road engine larger than 100 hp, that engine shall be equipped with a	
		catalyzed diesel particulate filter (soot	
		filter), unless certified by engine	
		manufacturers or the on-site AQCMM	
		that the use of such devices is not	
		practical for specific engine types. d)	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		The use of a soot filter may be terminated immediately if one of the following conditions exists, provided that the CPM is informed within ten (10) working days of the termination: (1) The use of the soot filter is excessively reducing normal availability of the construction equipment due to increased downtime for maintenance, and/or reduced power output due to an excessive increase in backpressure. (2) The soot filter is causing or is reasonably expected to cause significant engine damage. (3) The soot filter is causing or is reasonably expected to cause a significant risk to workers or the public. (4) Any other seriously detrimental cause which has the approval of the CPM prior to the termination being implemented. e) All heavy earthmoving equipment and heavy duty construction related trucks with engines meeting the requirements of (c) above shall be properly maintained and the engines tuned to the engine manufacturer's specifications. f) All diesel heavy construction equipment shall not remain running at idle for more than five minutes, to the	
Air Quality (and Public Health) - Operation	<ul> <li>PROJECT-SPECIFIC: During worst-case startup and full load operations, the facility will potentially contribute to the existing PM10 and PM2.5 violations exceeding 200 percent of the ambient air quality standard. The air dispersion modeling predicted the locations of the 50 highest PM10/PM2.5 ambient air quality impacts between 1.6 and 2.0 kilometers (or 1.0 and 1.3 miles) to the North-Northeast of the project site.</li> <li>All project mass daily emissions of nonattainment criteria pollutants and their precursors (NOx, VOC, CO, PM10, PM2.5, and SO2) are considered</li> </ul>	extent practical. AQ-SC6 The project owner shall submit to the CPM for review and approval any modification proposed by the project owner to any project air permit. The project owner shall submit to the CPM any modification to any permit proposed by the District or U.S. EPA, and any revised permit issued by	Mitigated to less than significant.

Environmental Topic	Impact(s)	Mitigation	Conclusion
	significant.	the District or U.S. EPA, for the	
	The results of the modeling analysis show that fumigation impacts will not	project.	
	violate any of the one-hour standards. Therefore, staff finds the potential	AQ-SC7 The project owner shall	
	ambient air quality impacts from fumigation to be less than significant.	provide emission reduction credits to	
	The modeling reflects the NOx and CO emission rates presented and shows	offset turbine exhaust and emergency	
	that there is no reasonable expectation that the emissions from initial	equipment NOx, VOC, SOx, PM10 and	
	commissioning will cause or contribute to an exceedance of the limiting	PM2.5 emissions in the form and	
	ambient air quality standards.	amount required by the District.	
	Because of the known relationship of NOx and VOC emissions to ozone	RECLAIM Trading Credits (RTCs)	
	formation, it can be said that the emissions of NOx and VOC from the	shall be provided for NOx as is	
	project do have the potential (if left unmitigated) to contribute to higher	necessary to demonstrate compliance	
	ozone levels in the region. These impacts would be significant because they	with Condition of Certification AQ-16.	
	would contribute to ongoing violations of the state and federal ozone	Emission reduction credits (ERCs) or	
	ambient air quality standards.	SCAQMD Priority Reserve Credits	
	Because of the known relationship of NOx and SOx emissions to PM2.5 formation, it can be said that the emissions of NOx and SOx from the	(PRCs) shall be provided for SOx (45 lb/day) and PM10 (463 lb/day).	
	PROJECT do have the potential (if left unmitigated) to contribute to higher	Emission reduction credits only shall	
	PM2.5 levels in the region.	be provided for VOC (225 lb/day,	
	CEC staff finds the potential ambient air visibility impacts Class 1 PSD	includes an offset ratio of 1.2).	
	areas from the exhaust emissions of the project to be less than significant.	AQ-SC9 If the project owner does not	
	The chronic hazard index for the maximally exposed individual is 0.026	participate in the voluntary California	
	while the maximum hazard index for acute effects is 0.012. These values	Climate Action Registry, then the	
	are well below CEC staff's significance criterion of 1.0, suggesting that the	project owner shall report on a	
	pollutants in questions are unlikely to pose a significant risk of chronic or	quarterly basis to the CPM the quantity	
	acute noncancer health effects anywhere in the project area.	of greenhouse gases (GHG) emitted as	
	The cancer risk to the maximally exposed individual from normal project	a direct result of facility electricity	
	operation is shown as 1.28 in a million, which is well below staff's	production as follows: The project	
	significance criterion of 10 in one million for this screening level	owner shall maintain a record of fuel	
	assessment. Thus, project-related cancer risk from routine operations would	use in units of million-Btu (MMBtu)	
	be less than significant for all individuals in the project area.	for all fuels burned on site for the	
	With the use of an aggressive antibacterial program, coupled with routine	purpose of power production. These	
	monitoring and biofilm removal, the chances of Legionella growth and	fuels shall include but are not limited	
	dispersal from the cooling towerswould be reduced to less than significant.	to: (1) all fuel burned in the combustion	
		turbines, (2) HRSGs (if applicable) or	
	<b>CUMULATIVE:</b> The results of the modeling effort to analyze cumulative	auxiliary boiler (if applicable), and (3)	
	air quality impacts show that the project will contribute to existing	all fuels used in any capacity for the	
	violations of the PM10 and PM2.5 ambient air quality standards.	purpose of turbine startup, shutdown,	
	The revised modeling results also show that the project will not contribute	operation or emission controls.	
	to violations of the 1-hour NO2 State Ambient Air Quality Standard.	AQ-SC10 The project owner shall	

Environmental Topic	Impact(s)	Mitigation	Conclusion
	Because of the known relationship of NOx and VOC emissions to ozone formation, it can be said that the emissions of NOx and VOC from the project do have the potential (if left unmitigated) to contribute to higher ozone levels in the region. These impacts would be significant because they would contribute to ongoing violations of the state and federal ozone ambient air quality standards. because of the known relationship of NOx and SOx emissions to PM2.5 formation, it can be said that the emissions of NOx and SOx from the project do have the potential (if left unmitigated) to contribute to higher PM2.5 levels in the region. CEC staff recommends condition of certification AQ-SC9, which requires the project owner to report the quantities of relevant greenhouse gases emitted as a result of electric power production (no conclusion regarding significance identified). The worst-case long-term non-cancer health impact from the project (represented as a chronic hazard index of 0.026) is well below staff's significance level of 1.0 at the location of maximum impact. At this level, staff does not expect any cumulative health impacts to be significant. As with cancer risk, long-term hazard would be lower at all other locations and cumulative impacts at other locations would also be less than significant.	submit to the CPM Quarterly Operation Reports, following the end of each calendar quarter, that include operational and emissions information as necessary to demonstrate compliance with the Conditions of Certification herein. The Quarterly Operation Report will specifically note or highlight incidences of noncompliance. AQ-SC11 The project owner shall perform quarterly cooling tower recirculating water quality testing, or shall provide for continuous monitoring of conductivity as an indicator, for total dissolved solids content. AQ-SC12 The cooling tower daily PM10 emissions shall be limited to 10.7 lb/day. The cooling tower shall be equipped with a drift eliminator to control the drift fraction to 0.0005 percent of the circulating water flow. The project owner shall estimate daily PM10 emissions from the cooling tower using the water quality testing data or continuous monitoring data and daily circulating water flow data collected on a quarterly basis. Compliance with the cooling tower PM10 emission limit shall be demonstrated as follows: PM10 = cooling water recirculation rate * total dissolved solids concentration in the blowdown water * design drift rate. AQ-1 The project owner shall limit the emissions from each gas fired combustion turbine train exhaust stacks in the amounts listed in this mitigation measure. AQ-2 The project owner/operator shall	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		not produce emissions of oxides of	
		nitrogen from the facility, including the	
		firewater pump and all five gas turbines combined, that exceed the RECLAIM	
		Trading Credits holdings required in	
		Condition of Certification AQ-16	
		within a calendar year.	
		AQ-3 The 2.5 ppm NOx emission limit,	
		2.0 ppm VOC emission limit and the	
		6.0 ppm CO emission limit shall not	
		apply during turbine commissioning,	
		start-up and shutdown. The	
		commissioning period shall not exceed	
		134 operating hours per turbine from	
		the initial start-up. Following	
		commissioning, start-ups shall not	
		exceed 60 minutes and the number of	
		start-ups shall not exceed 350 per year.	
		Following commissioning, shutdowns shall not exceed 10 minutes and the	
		number of shutdowns shall not exceed	
		one per day per turbine.	
		AQ-4 The 2.5 ppm NOx emissions	
		limit(s) are averaged over 60 minutes at	
		15 percent oxygen, dry basis. The 6.0	
		ppm CO emission limit(s) are averaged	
		over 60 minutes at 15 percent oxygen,	
		dry basis. The 2.0 ppm VOC emission	
		limit(s) are averaged over 60 minutes at	
		15 percent oxygen, dry basis.	
		The 5.0 ppm NH3 emission limit(s) are	
		averaged over 60 minutes at 15 percent	
		oxygen, dry basis. AQ-5 The project owner may at no	
		time purposefully exceed either the	
		mass or	
		concentration emission limits set forth	
		in Conditions of Certification AQ-1, -2,	
		-3 or -4.	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		AQ-6 The project owner shall limit the	
		fuel usage from each turbine to no	
		more than 393 mmscf of pipeline	
		quality natural gas in any one month.	
		The operator shall install and maintain a fuel flow meter and recorder to	
		accurately indicate and record the fuel	
		usage being supplied to each turbine.	
		AQ-7 The project owner shall conduct	
		an initial source test and annually	
		thereafter for NOx, CO and NH3 and	
		annually thereafter for SOx, VOC and	
		PM10 of each gas turbine exhaust stack	
		in accordance with the following	
		requirements:	
		• The project owner shall submit a	
		source test protocol to the District and	
		the CPM 45 days prior to the proposed	
		source test date for approval. The	
		protocol shall include the proposed	
		operating conditions of the gas turbine,	
		the identity of the testing lab, a	
		statement from the lab certifying that it meets the criteria of District Rule 304,	
		and a description of all sampling	
		and analytical procedures.	
		The initial source test shall be	
		conducted no later than 180 days	
		following the date of first fire.	
		• The District and CPM shall be	
		notified at least 10 days prior to the	
		date and time of the source test.	
		• The source test shall be conducted	
		with the gas turbine operating under	
		maximum, average and minimum	
		loads.	
		• The source test shall be conducted to	
		determine the oxygen levels in the	
		exhaust.	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		• The source test shall measure the fuel	
		flow rate, the flue gas flow rate and the	
		<ul><li>turbine generating output in MW.</li><li>The source test shall be conducted for</li></ul>	
		• The source test shall be conducted for the pollutants listed using the methods,	
		averaging times, and test locations	
		indicated and as approved	
		by the CPM	
		• The source test results shall be	
		submitted to the District and the CPM	
		no later than 60 days after the source	
		test was conducted.	
		• Exhaust flow rate shall be expresses	
		in terms of dry standard cubic feet per	
		minute and dry actual cubic feet per	
		minute.	
		• All moisture concentrations shall be expressed in terms of percent corrected	
		to 15 percent oxygen.	
		AQ-8 The project owner shall conduct	
		source testing of each gas turbine	
		exhaust	
		stack in accordance with the following	
		requirements:	
		• The project owner shall submit a	
		source test protocol to the District and	
		the CPM no later than 45 days prior to	
		the proposed source test date for	
		approval. The protocol shall include the	
		proposed operating conditions of the gas turbine, the identity of the testing	
		lab, a statement from the lab certifying	
		that it meets the criteria of District Rule	
		304, and a description of all sampling	
		and analytical procedures.	
		• Ammonia source testing shall be	
		conducted quarterly for the first 12	
		months of operation and annually	
		thereafter.	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		• NOx concentrations as determined by	
		CEMS shall be simultaneously	
		recorded during the ammonia test. If the NOx CEMS is inoperable, a test	
		shall be conducted to determine the	
		NOx emission by using District	
		Method 100.1 measured over a 60	
		minute time period.	
		• Source testing shall be conducted to	
		determine the ammonia emissions from	
		each gas turbine exhaust stack using	
		District Method 5.3 and 207.1 or EPA	
		Method 17 measured over a 1 hour	
		averaging period at the outlet of the SCR.	
		• The District and CPM shall be	
		notified of the date and time of the	
		source testing at least 7 days prior to	
		<ul><li>the test.</li><li>The source test shall be conducted</li></ul>	
		and the results submitted to the District	
		and CPM within 45 days after the test	
		date.	
		• Source testing shall measure the fuel	
		flow rate, the flue gas flow rate and the	
		gas turbine generating output.	
		• The test shall be conducted when the	
		equipment is operating at 80 percent	
		load or greater.	
		AQ-9 The project owner shall install	
		and maintain a CEMS in each exhaust	
		stack of the combustion turbine trains to measure the following parameters:	
		NOx concentration in ppmv and CO	
		concentration in ppmv. Concentrations	
		shall be corrected to 15 percent oxygen	
		on a dry basis. The CEMS will convert	
		the actual CO concentrations to mass	
		emission rates (lb/hr) and record the	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		hourly emission rates on a continuous	
		basis. The CEMS shall be installed and	
		operated to measure CO concentration	
		over a 15minute averaging time period.	
		The CEMS shall be installed and	
		operated in accordance with an	
		approved District Rule 218 CEMS plan	
		application and the requirements of Rule 2012. The CO CEMS shall be	
		installed and operating no later than 90	
		days after initial start-up of the turbine.	
		The NOx CEMS shall be installed and	
		operating no later than 12 months after	
		initial start-up of the turbine. During	
		the interim period between the initial	
		start-up and the provisional	
		certification date of the CEMS, the	
		project owner shall comply with the	
		monitoring requirements of Rule 2012	
		(h)(2) and Rule 2012 (h)(3). Within	
		two weeks of the turbine start-up date,	
		the project owner shall provide written	
		notification to the District of the exact	
		date of start-up.	
		AQ-10 The project owner shall keep	
		records in a manner approved by the	
		District for the following items:	
		Natural Gas use after CEMS	
		certification; Natural Gas use during	
		the commissioning period; and Natural	
		Gas use after the commissioning period and prior to the CEMS certification.	
		AQ-11 The owner/operator shall	
		determine the hourly ammonia slip	
		emissions from each exhaust stack for	
		each gas turbine train individually.	
		AQ-12 The operator shall install and	
		maintain an ammonia injection flow	
		meter and recorder to accurately	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		indicate and record the ammonia	
		injection flow rate being supplied to	
		each turbine. The device or gauge shall	
		be accurate to within plus or minus 5	
		percent and shall be calibrated once every twelve months.	
		AQ-13 The operator shall install and	
		maintain a temperature gauge and	
		recorder to accurately indicate and	
		record the temperature in the exhaust as	
		the inlet of the SCR reactor. The gauge	
		shall be accurate to within plus or	
		minus 5 percent and shall be calibrated	
		once every twelve months.	
		AQ-14 The operator shall install and	
		maintain a pressure gauge and recorder	
		to accurately indicate and record the	
		pressure differential across the SCR	
		catalyst bed in inches of water column.	
		The gauge shall be accurate to within	
		plus or minus 5 percent and shall be	
		calibrated once every twelve months.	
		AQ-15 The project owner shall limit the operating time of the firewater	
		pump to no more than 199.99 hours per	
		year. The firewater pump shall be	
		equipped with a non-resettable elapsed	
		meter to accurately indicate the elapsed	
		operating time of the engine. The	
		firewater pump shall be equipped with	
		a nonresettable totalizing fuel meter to	
		accurately indicate the fuel usage of the	
		engine. The firewater pump shall burn	
		only diesel fuel that contains sulfur	
		compounds less than or equal to 15	
		ppm by weight.	
		AQ-16 The project equipment shall not	
		be operated unless the project owner	
		demonstrates to the SCAQMD	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		Executive Officer that the facility holds sufficient RTCs to offset the prorated annual emissions increase for the first compliance year of operation. In addition, this equipment shall not be operated unless the project owner demonstrates to the Executive Officer that, at the commencement of each compliance year after the first compliance year of operation, the facility hold sufficient RTCs in an amount equal to the annual emission increase. The project owner shall submit all such information to the CPM for approval.	
Biological Resources - Construction	<b>PROJECT-SPECIFIC</b> : Onsite construction laydown and parking areas will occupy approximately 2 acres and be within existing site boundaries. Offsite laydown and parking areas will utilize 6.7 acres of ruderal habitat located in the Southern California Edison (SCE) transmission corridor north of the plant site. Parking and equipment staging areas required during the construction period will be located on previously disturbed sites containing no natural vegetation and provides no habitat to sensitive species. CEC Staff concluded, therefore, there will not be a significant impact to biological resources. Because a new line will be located in an area that contains no natural vegetation and provides no habitat to sensitive biological resources are expected to occur during construction of the new transmission line. CEC staff concluded that there will not be a significant impact to biological resources are expected to occur during construction of the new transmission line. CEC staff concluded that there will not be a significant impact to biological resources during construction of the natural gas, sewer, or water supply pipelines. The proposed project would be located within an existing developed area, and no sensitive species that could be impacted by additional noise are known to occur in the immediate vicinity. Therefore, CEC staff concluded there will be no significant impacts to biological resources by any increase or additional noise.	CEC staff concludes that impacts to biological resources during construction will not occur so mitigation will not be required. Public Health-1 The project owner shall develop and implement a Cooling Water Management Plan to ensure that the potential for bacterial growth in cooling water is controlled is controlled. The Plan shall be consistent with either Staff's "Cooling Water Management Program Guidelines" or with the Cooling Technology Institute's "Best Practices for Control of Legionella" guidelines.	Less than significant.

Environmental Topic	Impact(s)	Mitigation	Conclusion
Biological Resources - Operation	CUMULATIVE: None identified in the document. PROJECT-SPECIFIC: The project site would permanently occupy approximately 11.5 acres of existing industrial land. Because the entire site is paved and does not contain any vegetation or habitat to support sensitive species, CEC staff concluded there will not be a significant impact to biological resources. Since the proposed project would be located within an existing developed area, and no sensitive species that would be impacted by additional noise, light, etc., are known to occur in the immediate vicinity, staff concludes there will be no significant impact to biological resources. Overhead transmission lines can increase the potential for bird collisions and electrocutions.	BIO-1 The project owner shall design, install, and maintain transmission lines and all electrical components in accordance with the Avian Power Line Interaction Committee, Suggested Practices for Raptor Protection on Power Lines: The State of the Art in 1996, to reduce the likelihood of electrocutions of large birds.	Less than significant.
	<b>CUMULATIVE:</b> The project is not expected to result in significant biological resources impacts and there are no other proposed or currently operating projects in the study area that would contribute to any cumulative impacts, such as habitat loss, for sensitive species.		
Cultural Resources Construction	<ul> <li>PROJECT-SPECIFIC: it is possible that prehistoric and historic archaeological deposits could be encountered during construction, after the depth of fill, which varies from 4 to 6.5 feet over the project site, is exceeded.</li> <li>Construction of the project at this location would not affect the setting of structures or buildings.</li> <li>If archaeological sites are discovered, there is a potential for ethnographic/heritage impacts.</li> <li>CUMULATIVE: Staff's proposed conditions of certification will ensure that the proposed project's incremental effect is not cumulatively considerable.</li> </ul>	CUL-1 Prior to the start of pre- construction site mobilization; construction ground disturbance; construction grading, boring, and trenching; and construction, the project owner shall obtain the services of a Cultural Resources Specialist (CRS), and one or more alternates, if alternates are needed, to manage all monitoring, mitigation, and curation activities. The CRS may elect to obtain the services of Cultural Resource Monitors (CRMs) and other technical specialists, if needed, to assist in monitoring, mitigation, and curation activities. The project owner shall ensure that the CRS makes recommendations regarding the eligibility to the California Register of Historic Resources (CRHR) of any cultural resources that are newly	Mitigated to less than significant.

Environmental Topic	Impact(s)	Mitigation	Conclusion
		discovered or that may be affected in	
		an unanticipated manner. No ground	
		disturbance shall occur prior to Compliance Project Manager (CPM)	
		approval of the CRS, unless	
		specifically approved by the CPM.	
		Approval of a CRS may be denied or	
		revoked for non-compliance on this or	
		other projects.	
		CUL-2 Prior to the start of pre-	
		construction site mobilization;	
		construction ground disturbance;	
		construction grading, boring, and	
		trenching; and construction, if the CRS	
		has not previously worked on the	
		project, the project owner shall provide	
		the CRS with copies of the AFC and any confidential cultural resources	
		reports for the project. The project	
		owner shall also provide the CRS and	
		the CPM with maps and drawings	
		showing the footprint of the power	
		plant and all linear facilities. Maps	
		shall include the appropriate USGS	
		quadrangles and a map of the proposed	
		plant site and linear facilities at an	
		appropriate scale (e.g., 1:200 or 1" =	
		20') for plotting archaeological	
		features. If the CRS requests	
		enlargements for the plant site or strip	
		maps for linear facility routes, the project owner shall provide copies to	
		the CRS and CPM. The CPM shall	
		review submittals and, in consultation	
		with the CRS, approve those maps and	
		drawings that are appropriate for use in	
		cultural resources planning activities.	
		No ground disturbance shall occur prior	
		to CPM approval of maps and	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		drawings, unless specifically approved by the CPM. CUL-3 Prior to the start of pre- construction ground disturbance; construction grading, boring, and trenching; and construction, the project owner shall submit the Cultural Resources Monitoring and Mitigation Plan (CRMMP), as prepared by (or its preparation overseen by) the CRS, to the CPM for approval. The CRMMP shall be provided in the Archaeological Resource Management Report (ARMR) format, and, per ARMR guidelines, the author's name shall appear on the title page of the CRMMP. The CRMMP shall identify general and specific measures to minimize potential impacts to sensitive cultural resources. Implementation of the CRMMP shall be the responsibility of the CRS and the project owner. Copies of the CRMMP shall reside with the CRS, alternate CRS, each monitor, and the project owner's on- site manager. No ground disturbance shall occur prior to CPM approval of the CRMMP, unless specifically approved by the CPM. The CRMMP shall include, but not be limited to, the following elements and measures: 1. A proposed research design that includes a discussion of archaeological	
		research questions and testable hypotheses specifically applicable to the project area and a discussion of artifact collection, retention/disposal,	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		and curation policies as functions of the	
		research questions formulated in the	
		research design. A prescriptive	
		treatment plan may be included in the CRMMP for limited resource types.	
		The following statement shall be added	
		to the CRMMP's Introduction: "Any	
		discussion, summary, or paraphrasing	
		of the conditions of certification in this	
		CRMMP is intended as general	
		guidance and as an aid to the user in	
		understanding the conditions and their	
		implementation. If there appears to be	
		any conflict between the conditions and	
		the way in which they have been	
		summarized, described, or interpreted	
		in the CRMMP, the conditions, as written in the Energy Commission's	
		Final Decision, supersede any	
		interpretation of the conditions in the	
		CRMMP." The Cultural Resources	
		conditions of certification shall be	
		attached as an appendix to the	
		CRMMP.	
		3. Specification of the implementation	
		sequence and the estimated time frames	
		needed to accomplish all project-related	
		archaeological tasks during ground	
		disturbance, construction, and post-	
		construction analysis phases of the	
		project. 4. Identification of the	
		person(s) expected to perform each of the archaeological tasks, their	
		responsibilities, and the reporting	
		relationships between project	
		construction management and the	
		mitigation and	
		monitoring team.	
		5. A discussion of the inclusion of	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		Native American observers or	
		monitors, the procedures to be used to	
		select them, and their role and	
		responsibilities.	
		6. A discussion of all avoidance	
		measures (such as flagging or fencing)	
		which will be used to prohibit or	
		otherwise restrict access to sensitive	
		cultural resource areas that are, or, once	
		discovered, may need to be avoided	
		during construction and/or operation, and identification of areas where these	
		measures may be implemented. The	
		discussion shall address how these	
		measures would be implemented prior	
		to the start of construction, or after	
		discovery, and how long they would be	
		needed to protect the resources from	
		project-related effects.	
		7. A discussion of the requirement that	
		all cultural resources encountered that	
		cannot be treated prescriptively shall be	
		recorded on a DPR form 523, mapped,	
		and photographed. In addition, a	
		discussion shall be included of the	
		requirement that all records produced	
		and all archaeological materials	
		collected and retained as a result of the	
		archaeological investigations (survey,	
		testing, monitoring, and data recovery)	
		shall be curated in accordance with the	
		State Historical Resources	
		Commission's "Guidelines for the	
		Curation of Archaeological	
		Collections," in a retrievable storage	
		collection in a public repository or	
		museum. The public repository or museum must meet the standards and	
		requirements for the curation of	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		cultural resources set forth at Title 36	
		of the Code of Federal Regulations, Part 79.	
		8. A discussion of any requirements,	
		specifications, or funding needed for	
		the curation of the materials to be	
		delivered for curation and how	
		requirements, specifications, and	
		funding shall be met. This shall include	
		information indicating that the project	
		owner will pay all curation fees and	
		state that any agreements concerning	
		curation will be retained and be	
		available for audit for the life of the	
		project. Also, the name and phone	
		number of the contact person at the curating institution shall be provided.	
		9. A discussion of the availability of	
		and the designated specialist's access to	
		equipment and supplies necessary for	
		photographing and site mapping, and	
		for recovering, recording, and	
		photographing all cultural materials	
		encountered during construction that	
		cannot be treated prescriptively.	
		10. A discussion of the required	
		Cultural Resources Report.	
		CUL-4 The project owner shall submit	
		the Cultural Resources Report (CRR) to the CPM for approval. The CRR	
		shall be written by the CRS and shall	
		be provided in the ARMR format. The	
		CRR shall report on all field activities	
		including dates, times, locations,	
		samplings, analyses, and findings. All	
		survey reports, Department of Parks	
		and Recreation (DPR) 523 forms, and	
		additional research reports not	
		previously submitted to the California	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		Historical Resources Information	
		System (CHRIS) and the State Historic	
		Preservation Officer (SHPO) shall be included as an appendix to the CRR. If	
		the ARMR reports have previously	
		been sent to the CHRIS, then receipt	
		letters from the CHRIS shall be	
		included in an appendix. If the	
		technical report originally prepared for	
		this project, has not been submitted to	
		the CHRIS, append it to the CRR. If no	
		technical report was prepared for the	
		siting phase of this project, the cultural	
		resources information collected for the	
		siting phase of the project shall be incorporated into this CRR.	
		CUL-5 Prior to and during the start of	
		pre-construction site mobilization;	
		construction ground disturbance;	
		construction grading, boring, and	
		trenching; and construction (including	
		landscaping), the project owner shall	
		provide Worker Environmental	
		Awareness Program (WEAP) training	
		to all new workers within their first	
		week of employment. The training shall	
		be prepared by the CRS, may be conducted by any member of the	
		archaeological team, and may be	
		presented in the form of a video. The	
		CRS shall be available (by telephone or	
		in person) to answer questions posed by	
		employees	
		CUL-6 The project owner shall ensure	
		that the CRS, alternate CRS, or CRMs	
		shall monitor pre-construction site	
		mobilization; construction ground	
		disturbance; construction grading;	
		boring, and trenching; and construction	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		(including landscaping), full-time at the	
		project site where ground disturbance	
		or excavations exceed three feet and for	
		the full width and length of excavations	
		for linear facilities where the ground	
		disturbance or excavation exceeds three	
		feet, to ensure there are no impacts to	
		undiscovered cultural resources and to	
		ensure that known cultural resources	
		are not impacted in an unanticipated	
		manner. If ground disturbance becomes	
		necessary at any ancillary areas,	
		fulltime monitoring shall be conducted	
		there as well. Full-time archaeological monitoring is defined as archaeological	
		monitoring of all earth-moving	
		activities on a construction site for as	
		long as the activities are ongoing.	
		Fulltime archaeological monitoring	
		may require one monitor per active	
		earthmoving machine working in	
		archaeologically sensitive areas. After	
		examining the soils, if the CRS	
		determines that full-time monitoring is	
		not necessary in certain locations, a	
		letter or e-mail providing a detailed	
		justification for the decision to reduce	
		the level of monitoring shall be	
		provided to the CPM for review and	
		approval at least 24 hours prior to any	
		reduction in monitoring.	
		CUL-7 A Native American monitor or	
		monitors shall be obtained to monitor	
		preconstruction site mobilization,	
		construction ground disturbance,	
		construction grading, boring, trenching	
		and construction (including	
		landscaping) in areas where ground	
		disturbance exceeds three feet and	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		Native American artifacts may be	
		discovered as identified by the CRS.	
		Lists of concerned Native Americans, with contact information,	
		and guidelines for monitoring shall be	
		obtained from the Native American	
		Heritage Commission. Preference in	
		selecting a monitor or monitors shall be	
		given to Native Americans with	
		traditional ties to the area that shall be	
		monitored.	
		CUL-8 The project owner shall grant	
		authority to halt construction to the	
		CRS, alternate CRS, and the CRMs in	
		the event previously unknown cultural	
		resources sites or materials are	
		encountered (discovery), or if known resources may be impacted in a	
		previously unanticipated manner.	
		Redirection of ground disturbance	
		(including landscaping) shall be	
		accomplished under the direction of the	
		construction supervisor in consultation	
		with the CRS. In the event cultural	
		resources are found or impacts can be	
		anticipated, construction shall be halted	
		or redirected in the immediate vicinity	
		of the find and shall remain halted or	
		redirected until all of the following	
		have occurred: 1. The CRS has notified the project	
		owner and the CPM has been notified	
		within 24 hours of the discovery, or by	
		the following Monday morning if the	
		cultural resources discovery occurs	
		between 8:00 AM on Friday and 8:00	
		AM on Sunday. Notification to the	
		CPM must include a description of the	
		discovery (or changes in character or	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		attributes), the action taken (i.e., work stoppage or redirection), a recommendation of eligibility, and recommendations for mitigation of any cultural resources discoveries, whether or not a determination of significance has been made. 2. The CRS has completed field notes, measurements, and photography for a Department of Parks and Recreation (DPR) 523 primary form for all cultural materials that cannot be treated prescriptively. The 523 primary form will include in the Description entry a recommendation of the significance of the find. The completed forms shall be submitted to the CPM. 3. The CRS and the project owner have consulted with the CPM, and the CPM has concurred with the recommended eligibility of the discovery and approved the CRS's proposed data recovery, including the curation of the artifacts, or other appropriate mitigation; and 4. Any necessary data recovery and mitigation has been completed.	
Cultural Resources Operation	<ul> <li>PROJECT-SPECIFIC: During operation of the proposed power plant, if a leak should develop in the gas or water pipelines supplying the plant, repair of the buried utility could require the excavation of a large hole. Such repairs could impact previously unknown subsurface archaeological resources in areas unaffected by the original trench excavation.</li> <li>CUMULATIVE: Staff's proposed conditions of certification will ensure that the proposed project's incremental effect is not cumulatively considerable.</li> </ul>	Same as for construction	Mitigated to less than significant.

Environmental Topic	Impact(s)	Mitigation	Conclusion
Geology (and Paleontology)- Construction	<ul> <li>PROJECT-SPECIFIC: Since construction of the proposed project will still include significant grading, foundation excavation, and utility trenching, staff considers the probability that paleontological resources will be encountered to be high in deeper excavations, based on SVP assessment criteria.</li> <li>CUMULATIVE: It is CEC staff's opinion that the potential for significant adverse cumulative impacts from geologic hazards, and to potential geologic, mineralogic, and paleontologic resources resulting from construction of the proposed project is very low.</li> </ul>	PAL-1 The project owner shall provide the Compliance Project Manager (CPM) with the resume and qualifications of its Paleontological Resource Specialist (PRS) for review and approval. If the approved PRS is replaced prior to completion of project mitigation and submittal of the Paleontological Resources Report, then the project owner shall obtain CPM approval of the replacement PRS. The project owner shall submit to the CPM to keep on file, resumes of the qualified Paleontological Resource Monitors (PRMs). If a PRM is replaced, the resume of the replacement PRM shall also be provided to the CPM. PAL-2 The project owner shall provide to the PRS and the CPM, for approval, maps and drawings showing the footprint of the power plant, construction laydown areas, and all related facilities. Maps shall identify all areas of the project where ground disturbance is anticipated. If the PRS requests enlargements, the project owner shall provide copies to the PRS and CPM. The site grading plan and the plan and profile drawings for the utility lines would be acceptable for this purpose. The plan drawings should show the location, depth, and extent of all ground disturbances and can be at a scale of 1 inch = 20 feet to 1 inch = 100 feet range. If the footprint of the power plant changes, then the project owner shall provide maps and drawings reflecting these changes to the PRS and CPM. Maps and drawings may be	Mitigated to less than significant.

Environmental Topic	Impact(s)	Mitigation	Conclusion
		limited to the boundaries of the project	
		project.	
		PAL-3 The project owner shall ensure	
		that the PRS prepares, and the project owner submits to the CPM for review	
		and approval, a Paleontological	
		Resources Monitoring and Mitigation	
		Plan (PRMMP) to identify general and	
		specific measures to minimize potential	
		impacts to significant paleontological	
		resources. Approval of the PRMMP by	
		the CPM shall occur prior to any	
		ground disturbance. The PRMMP shall	
		function as the formal guide for	
		monitoring, collecting and sampling	
		activities and may be modified with	
		CPM approval. This document shall be used as a basis for discussion in the	
		event that on-site decisions or changes	
		are proposed. Copies of the revised	
		PRMMP shall reside with the PRS,	
		each monitor, the project owner's on-	
		site manager, and the CPM.	
		PAL-4 Prior to ground disturbance and	
		for the duration of construction	
		activities involving ground disturbance	
		deeper than 5 feet, the project owner	
		and the PRS shall prepare and conduct	
		weekly CPM-approved training for all	
		workers, including but not limited to, project managers, construction	
		supervisors, foremen, and general	
		workers who are involved with or	
		operate ground disturbing equipment or	
		tools. Workers shall not excavate in	
		sensitive units prior to receiving CPM-	
		approved worker training. Worker	
		training shall consist of an initial in-	
		person PRS training session during the	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		project kick-off. Following initial training, a CPM-approved video or in- person training may be used for new employees. The training program may be combined with other training programs prepared for cultural and biological resources, hazardous materials, or any other areas of interest or concern. No ground disturbance shall occur prior to CPM approval of the Worker Environmental Awareness Program (WEAP), unless specifically approved by the CPM. PAL-6 The project owner, through the designated PRS, shall ensure that all components of the PRMMP are adequately performed including collection of fossil materials, preparation of fossil materials for analysis, analysis of fossils, identification and inventory of fossils, the preparation of fossils for curation, and the delivery for curation of all significant paleontological resource materials encountered and collected during the project construction. PAL-7 The project owner shall ensure preparation of the Paleontological Resources Report (PRR) by the designated PRS. The PRR shall be prepared following completion of the ground disturbing activities. The PRR shall include an analysis of the collected fossil materials and related information and submitted to the CPM for review and approval.	
Geology (and Paleontology)- Operation	<b>PROJECT-SPECIFIC</b> : Ground shaking and liquefaction during an earthquake represent the only known geologic hazards at this site. These		Mitigated to less than significant

Environmental Topic	Impact(s)	Mitigation	Conclusion
	potential hazards can be effectively mitigated through facility design. No viable geologic or mineralogic resources are known to exist within the project site. The Walnut oil field is located approximately one mile to the east-northeast. Paleontological resources have not been documented on the project project site; however, undisturbed Tertiary to Pleistocene native materials could exhibit a high sensitivity rating with respect to containing significant paleontologic resources. No faults are mapped within the project parcel, or its planned transmission line easement. The likelihood of ground surface rupture at this site is, therefore, thought to be minimal. There may be at least a moderate potential for liquefaction on the project site. The potential for dynamic compaction is considered low based on the geotechnical exploration borings and analysis provided by the application The soils at the site are loose to medium dense but are thought to be of sufficient density so that risk for hydrocompaction is negligible. CEC staff has concluded that there is no significant potential for subsidence due to ground water or petroleum withdrawal at the proposed project. No landslides are present on or adjacent to the proposed energy facility footprint. Mapping by the Federal Emergency Management Agency (FEMA, 1994) does not show the project site to be within a flood zone. The proposed project site is not near any large body of water. As a result, the potential for tsunamis to affect the operation of the facility is considered negligible		
	adverse cumulative impacts from geologic hazards, and to potential geologic, mineralogic, and paleontologic resources resulting from operation of the proposed project is very low.		
Hazards and Hazardous Materials - Construction	<b>PROJECT-SPECIFIC:</b> During the construction phase of the project, the only hazardous materials proposed for use include paint, paint thinner, cleaners, solvents, sealants, gasoline, diesel fuel, motor oil, hydraulic fluid, lubricants, and welding flux. Any impact of spills or other releases of these materials will be limited to the site due to the small quantities involved, the infrequent use and hence reduced chances of release, and/or the temporary containment berms used by contractors. Petroleum hydrocarbon-based motor fuels, mineral oil, lube oil, and diesel fuel are all of very low volatility and represent limited offsite hazard even in larger quantities.		Less than significant

Environmental Topic	Impact(s)	Mitigation	Conclusion
Hazards and Hazardous	CUMULATIVE: None identified in the document. PROJECT-SPECIFIC: Sodium hypochlorite, sodium hypobromite,	HAZ-1 The project owner shall not use	Mitigated to less than
Materials – Operation	sodium hydroxide, and sulfuric acid will be stored on-site but do not pose a risk of off-site impacts because the volumes stored will be less than 2000 gallons, they have relatively low vapor pressures, and spills would be confined to the site. In 1995, staff conducted a quantitative assessment of the potential for impact associated with sulfuric acid use, storage, and transportation. CEC staff concluded that no hazard would be posed to the public due to the extremely low volatility of this aqueous solution of sulfuric acid. While natural gas will be used in significant quantities, it will not be stored on-site. The risk of a fire and/or explosion on-site can be reduced to insignificant levels through adherence to applicable codes and development and implementation of effective safety management practices. CEC staff has reviewed the applicant 's aqueous ammonia modeling calculations and conclusions. CEC staff believes that due to the engineering controls proposed by the applicant for the storage and transfer of aqueous ammonia, any potential accidental release of aqueous ammonia at the project site will not cause a significant impact and will not represent a significant risk to the public. Based on the environmental mobility, toxicity, quantities present at the site and frequency of delivery, it is CEC staff's opinion that aqueous mamonia poses the predominate risk associated with hazardous materials transportation and use at the proposed facility. CEC staff concludes that the risk associated with transportation of other hazardous materials to the proposed facility does not significantly increase the risk of impact beyond that associated with ammonia transportation. CEC staff determined that tank failures at the project site during seismic events are not probable and do not represent a significant risk to the public.	any hazardous materials not listed in Appendix C, or in greater quantities than those identified by chemical name in Appendix C, below, unless approved in advance by the Compliance Project Manager (CPM). HAZ-2 The project owner shall concurrently provide a Business Plan and a Risk Management Plan (RMP) to the Certified Unified Program Authority – (CUPA) (Los Angeles County Fire Department, Health Hazardous Materials Division) and the CPM for review at the time the RMP is first submitted to the U.S. Environmental Protection Agency (EPA). After receiving comments from the CUPA, the EPA, and the CPM, the project owner shall reflect all recommendations in the final documents. Copies of the final Business Plan and RMP shall then be provided to the CUPA and EPA for information and to the CPM for approval. HAZ-3 The project owner shall develop and implement a Safety Management Plan for delivery of aqueous ammonia. The plan shall include procedures, protective equipment requirements, training and a checklist. It shall also include a section describing all measures to be implemented to prevent mixing of	significant

Environmental Topic	Impact(s)	Mitigation	Conclusion
Topic		aqueous ammonia with incompatible hazardous materials. HAZ-4 The aqueous ammonia storage facility shall be designed to either the ASME Pressure Vessel Code and ANSI K61.6 or to API 620. In either case, the storage tank shall be protected by a secondary containment basin capable of holding 125 percent of the storage volume or the storage volume plus the volume associated with 24 hours of rain assuming the 25-year storm. The final design drawings and specifications for the ammonia storage tank and secondary containment basins shall be submitted to the CPM. HAZ-5 The project owner shall ensure that no flammable material is stored within 50 feet of the sulfuric acid tank. HAZ-6 The project owner shall direct all vendors delivering aqueous ammonia to the site to use only tanker truck transport vehicles that meet or exceed the specifications of U.S. DOT Code MC- 307. HAZ-7 The project owner shall direct all vendors delivering any hazardous material to the site to use only the route approved by the CPM (from State	
		Route 60, to North Azusa Avenue, to East Gale Avenue to Bixby Drive, to the project site). The project owner shall submit any desired change to the approved delivery route to the CPM for	
		review and approval. HAZ-8 At least 30 days prior to commencing construction, a site- specific Construction Site Security Plan	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		for the construction phase shall be prepared and made available to the CPM for review and approval. The Construction Security Plan shall include the following:	
		1. Perimeter security consisting of fencing enclosing the construction area;	
		2. Security guards;	
		3. Site access control consisting of a check-in procedure or tag system for construction personnel and visitors;	
		4. Written standard procedures for employees, contractors and vendors when encountering suspicious objects or packages on-site or off-site;	
		5. Protocol for contacting law enforcement and the CPM in the event of suspicious activity or emergency; and	
		6. Evacuation procedures.	
		HAZ-9 In order to determine the level of security appropriate for this power plant, the project owner shall prepare a Vulnerability Assessment and submit that assessment as part of the Operations Security Plan to the CPM for review and approval. The Vulnerability Assessment shall be prepared according to guidelines issued by the North American Electrical Reliability Council (NERC 2002), the U.S. Department of Energy (DOE 2002), and the U.S. Department of Justice Chemical Vulnerability Assessment Methodology (July 2002).	
		Physical site security shall be consistent with the guidelines issued by the NERC (Version 1.0, June 14, 2002)	

Impact(s)	Mitigation	Conclusion
	and the DOE (2002) and shall also be based, in part, on the use, storage, and quantity of hazardous materials present at the facility.	
<ul> <li>PROJECT-SPECIFIC: The applicant estimated that from water erosion, approximately 6.53 tons of soil could be eroded during construction and an additional 8.25 tons of soil could be eroded during grading, for a total soil loss of 14.78 tons if proposed BMPs are not implemented. The potential for greatest soil loss is from the Silty Loam, because it is more susceptible to erosion than clayey soils, and is the predominant soil type making-up about 90% of the project area for both the site and linear areas.</li> <li>CEC staff does not believe that construction will have an adverse impact on surface water hydrology or exacerbate flooding, if recommended BMP's are implemented and LORs are followed during the construction process.</li> <li>CEC staff concludes that no significant impact to wastewater will occur if the above mentioned mitigation measures are implemented.</li> <li>CEC staff believes the proposed construction scheduling and methods for erosion and drainage control, including the development of a Final DESCP consistent with Condition of Certification Soil and Water-1 and a SWPPP for Construction Activity in accordance</li> <li>CUMULATIVE: Activities related to the project would not result in cumulative impacts to water and soil resources.</li> </ul>	SOIL & WATER-1 Prior to site mobilization, the project owner shall obtain CPM approval for a site-specific Drainage, Erosion and Sedimentation Control Plan (DESCP) that ensures protection of water quality and soil resources of the project site and all linear facilities for both the construction and operational phases of the project. This plan shall address appropriate methods and actions, both temporary and permanent, for the protection of water quality and soil resources, demonstrate no increase in off-site flooding potential, meet local requirements, and identify all monitoring and maintenance activities. The plan shall be consistent with the grading and drainage plan as required by Condition of Certification CIVIL-1 and may incorporate by reference any Storm Water Pollution Prevention Plan (SWPPP) developed in conjunction with any NPDES permit. SOIL & WATER-2 The project owner shall comply with the requirements of the General National Pollutant Discharge Elimination System (NPDES) Permit for Discharges of Stormwater Associated with Construction Activity. The project owner shall develop and implement a Storm Water Pollution Prevention Plan	Mitigated to less than significant
a a lo g e 9 C s a C th C e c o f o C	<ul> <li><b>ROJECT-SPECIFIC:</b> The applicant estimated that from water erosion, pproximately 6.53 tons of soil could be eroded during construction and an dditional 8.25 tons of soil could be eroded during grading, for a total soil oss of 14.78 tons if proposed BMPs are not implemented. The potential for reatest soil loss is from the Silty Loam, because it is more susceptible to rosion than clayey soils, and is the predominant soil type making-up about 0% of the project area for both the site and linear areas.</li> <li>EC staff does not believe that construction will have an adverse impact on urface water hydrology or exacerbate flooding, if recommended BMP's re implemented and LORs are followed during the construction process.</li> <li>EC staff believes the proposed construction scheduling and methods for rosion and drainage control, including the development of a Final DESCP onsistent with Condition of Certification Soil and Water-1 and a SWPPP or Construction Activity in accordance</li> </ul>	ROJECT-SPECIFIC: The applicant estimated that from water erosion, pproximately 6.53 tons of soil could be eroded during construction and an diditional 8.25 tons of soil could be eroded during grading, for a total soil sosi of 14.78 tons if proposed BMPs are not implemented. The potential for brobin the site and linear areas.       SOIL & WATER-1 Prior to site mobilization, the project owner shall obtain CPM approval for a site-specific Drainage, Erosion and Sedimentation Control Plan (DESCP) that ensures protection of water quality and soil resources of the project area for both the site and linear areas.         EC staff does not believe that construction will have an adverse impact on significant impact to wastewater will occur if the above mentioned mitigation measures are implemented.       Sources of the project site and all linear facilities for both the grootection of water quality and soil resources, demonstrate to no increase in off-site flooding potential, meet local requirements, and identify all monitoring and maintenance activities. The plan shall be consistent with the grading and drainage point CIVL-1 and may incorporate by reference any Storm Water Pollution Prevention Plan (SWPPP) developed in conjunction with any NPDES permit.         VUMULATIVE: Activities related to the project would not result in unulative impacts to water and soil resources.       SWPPP) developed in conjunction with any NPDES permit.         SOIL & WATER-2 The project owner shall cevelop and implements of the General National Pollutant Discharge Elimination System (NPDES) Permit for Discharges of Stormwater Associated with Construction and operational polement a

Environmental Topic	Impact(s)	Mitigation	Conclusion
		entire project site, lay down area, and all linear facilities (Construction SWPPP), and shall submit copies to the CPM of all correspondence between the project owner and the RWQCB about the General NPDES permit.	
Hydrology and Water Quality (and Soils) - Operation	<ul> <li><b>PROJECT-SPECIFIC:</b> CEC staff believes adverse impacts to soil, and the potential for soil erosion, would not be significant during project operation.</li> <li>CEC staff does not believe operation of project would cause any significant adverse impact to surface hydrology or exacerbate flooding.</li> <li>CEC staff believes that there would not be a significant adverse impact on groundwater, or potential to spread contaminants in the groundwater, as a result of operation of the project.</li> <li>No impacts are anticipated from the selection of reclaimed water as the primary water source, or from the use of potable water as the back-up water source.</li> <li>No significant adverse impacts are expected from any project wastewater dischargeafter adoption and implementation of CEC staff's recommended conditions.</li> <li>Conditions of approval would include containment of hazardous material storage areas and roof covering of material storage areas. As a result of this mitigation, staff believes that there will be no significant adverse impacts associated with stormwater drainage during the operation of project.</li> <li><b>CUMULATIVE</b>: Activities related to the project would not result in cumulative impacts to water and soil resources.</li> </ul>	SOIL & WATER-3 The project owner shall comply with the requirements of the General National Pollutant Discharge Elimination System (NPDES) Permit for Discharges of Stormwater Associated with Industrial Activity. The project owner shall develop and implement a Storm Water Pollution Prevention Plan (SWPPP) for the operation of the entire project site (Operational SWPPP), and shall submit copies to the CPM of all correspondence between the project owner and the RWQCB about the General NPDES permit. SOIL & WATER-4 The project owner shall obtain a Flood Permit and Water Quality Agreement for commercial connection of the project's operational stormwater system to the County's flood control system from Los Angeles County Flood Control District/Department of Public Works. project shall comply with all stormwater discharge requirements, including pretreatment, peak flow restrictions, payment of fees, and monitoring and reporting requirements as applicable. The CPM shall be notified by the project owner in writing of any reported non-compliance with	Mitigated to less than significant

Environmental Topic	Impact(s)	Mitigation	Conclusion
Topic		the Water Quality Agreement's discharge requirements, including corrective measures for non- compliance and the results of implementing those measures. The project owner shall also prepare and comply with a Standard Urban Stormwater Mitigation Plan (SUSMP). SOIL & WATER-5 Prior to site mobilization, the project owner shall submit a Dual Plumbing Plan for using reclaimed and potable water to Rowland Water District and Los Angeles County Department of Health Services for review and approval. The Dual Plumbing Plan shall be prepared in accordance with Los Angeles County Department of Health Services requirements and Title 22 of	Conclusion
		the State Water Code. The project owner shall comply with any reporting and inspection requirements set forth by the County Department of Health Services to fulfill statutory requirements. Following site mobilization, the project owner shall submit a written summary in the Monthly Compliance Reports, reporting the status of the Dual Plumbing Plan's review by Rowland Water District and Los Angeles County Department of Health Services, and the plan's implementation. SOIL & WATER-6 The project owner shall use reclaimed water as its primary water supply for construction and operations, including cooling, process, and other approved non-potable uses.	

Environmental Topic	Impact(s)	Mitigation	Conclusion
Topic		Any proposed changes in water supply that could cause an increase in project's potable water use in excess of the limit specified in SOIL & WATER-7 must first be approved by the CPM. Prior to construction, the project owner shall install or obtain access to a service or hydrant for use of reclaimed water during construction for dust suppression, hydrostatic testing and all other non-potable uses. Prior to commercial operation, the project owner shall install and maintain metering devices as part of the project reclaimed and potable water supply and distribution system to monitor and record in gallons per day the total volumes of water supplied to the project from each water source. Those metering devices shall be operational for the life of the project. SOIL & WATER-7 The project owner shall not exceed 95 AF of potable water use per calendar year as emergency backup water supply, without written authorization from the CPM. The project owner shall monitor the use of emergency backup water and report estimated usage prior to any planned reclaimed water system outages, and report total usage to the CPM	
		immediately after any occurrence when potable water is used as a backup water source. Potable water shall not be used for cooling, process, or other approved non-potable uses when reclaimed water	
		is available. When necessary to use potable water for emergency backup supply, it shall not exceed the	

Environmental Topic	Impact(s)	Mitigation	Conclusion
		minimum amount required to allow for the re-introduction of reclaimed water as the main water supply source following disruption of reclaimed water service. The project owner shall report all disruptions to the reclaimed water service in the annual compliance report, including the cause, associated volume of potable water used, and the total annual use for the year and for two years prior. SOIL & WATER-8 The project owner shall secure a Water Supply Service Agreement for reclaimed and potable water service from Rowland Water District. The project owner shall report to the CPM any incidents of non- compliance with the service agreement (e.g. exceeding maximum delivery rates or annual volumes of potable and reclaimed water supply), corrective measures to avoid recurrence, and the results of implementing those measures. SOIL & WATER-9 The project owner	
		shall obtain a Permit for Industrial Wastewater Discharge and comply with the wastewater discharge limitations, pretreatment requirements, peak flow restrictions, dewatering discharges, payment of fees, and monitoring and reporting requirements of Los Angeles County Sanitation District.	
Land Use and Planning Construction	<ul><li><b>PROJECT-SPECIFIC:</b> None identified in the document.</li><li><b>CUMULATIVE:</b> None identified in the document.</li></ul>	None identified in the document.	None identified in the document.
Land Use and Planning	<b>PROJECT-SPECIFIC</b> : Neither the size nor nature of the project would result in a physical division or disruption of an established community. No	LAND-1 The project owner shall	Mitigated to less than

Environmental Topic	Impact(s)	Mitigation	Conclusion
Operation	<ul> <li>new physical barriers would be created by the project, and no existing roadways or pathways would be blocked.</li> <li>The proposed project is consistent with the following goals of the City of Industry General Plan: <ol> <li>Maintain and further develop an employment base in the San Gabriel Valley and the Los Angeles metropolitan area; and</li> <li>Accelerate and maintain a tax base that can support the overall growth potential of the area.</li> </ol> </li> <li>CUMULATIVE: CEC staff finds that the project would not by itself or cumulatively have an adverse effect on land use.</li> </ul>	<ul> <li>design and construct the project to the following design standards in the Development Plan Standards of the City of Industry's Development</li> <li>Guidelines (City Code Section 17.03.060):</li> <li>1. All buildings and structures shall be set back a minimum of 30 feet from the curb line of all streets.</li> <li>2. The maximum height of any building or structure permitted in any industrial zone shall be 150 feet.</li> <li>3. Lots or parcels consisting of 60,000 sq. ft. or more shall have a maximum building square footage of 50 percent of the total lot or parcel area.</li> <li>4. In the Industrial Zone (M), the number of parking spaces provided is one space per 500 sq. ft. of building floor area. The minimum size of each parking space shall be 9 feet in width by 19 feet in length; compact parking spaces which are at least 8 feet in width by 16 feet in length may constitute up to 20 percent of the required parking for all types of</li> </ul>	significant
Noise - Construction	<ul> <li>PROJECT-SPECIFIC: The construction noise levels may be audible at the above receptors but will not likely cause annoyance, as the construction activities will be temporary and will occur during specified daytime hours. The addition of construction noise to the ambient would result in 63 dBA, an increase of 5 dBA over the ambient level. Staff regards an increase of up to 5 dBA as a less-than-significant impact. Construction noise should not create an adverse impact at M2, the nearest sensitive receptor. Construction of linear facilities typically moves along at a rapid pace, thus not subjecting any one receptor to noise impacts for more than two or three</li> </ul>	NOISE-1 Prior to the start of ground disturbance, the project owner shall notify all residents within one-half mile of the site and the linear facilities, by mail or other effective means, of the commencement of project construction. At the same time, the project owner shall establish a telephone number for use by the public to report any undesirable noise conditions associated	Mitigated to less than significant

Environmental Topic	Impact(s)	Mitigation	Conclusion
	days. CEC staff believes pile driving would not result in significant vibration impacts at the nearby commercial buildings or the nearest sensitive receptors. No significant vibration impacts would result from the demolition project. <b>CUMULATIVE:</b> The demolition of the existing warehouse would occur prior to the start of the project construction activities and thus would not create any cumulative noise impacts when combined with this project. CEC staff is not aware of any other major construction or demolition activities that, when combined with this demolition project, would cause significant cumulative noise impacts.	with the construction and operation of the project. If the telephone is not staffed 24 hours per day, the project owner shall include an automatic answering feature, with date and time stamp recording, to answer calls when the phone is unattended. This telephone number shall be posted at the project site during construction in a manner visible to passersby. This telephone number shall be maintained until the project has been operational for at least one year. NOISE-2 Throughout the construction and operation of the project, the project owner shall document, investigate, evaluate, and attempt to resolve all project related noise complaints. NOISE-3 The project owner shall submit to the CPM for review and approval a noise control program. The noise control program shall be used to reduce employee exposure to high noise levels during construction and also to comply with applicable OSHA and Cal-OSHA standards.	
Noise - Operation	<ul> <li><b>PROJECT-SPECIFIC:</b> The project noise level of 52 dBA at M4 when combined with the ambient level of 44 dBA L90 at this location will result in 53 dBA L90, 9 dBA above the ambient. As explained above, staff considers this increase to be less than significant.</li> <li>The project operational noise impact at the school will be expected to be less than significant.</li> <li><b>CUMULATIVE:</b> None identified in the document</li> </ul>	NOISE-4 The project design and implementation shall include appropriate noise mitigation measures adequate to ensure that operation of the project will not cause noise levels attributable to plant operation, during the four quietest consecutive hours of the nighttime, to exceed an average of 52 dBA measured near the intersection of Fieldgate Avenue and Folger Street (monitoring location M2) or near the intersection of Inyo Street and Roxham	Mitigated to less than significant

Environmental Topic	Impact(s)	Mitigation	Conclusion
		Avenue (monitoring location M4). NOISE-5 Following the project first achieving a sustained output of 90 percent or greater of rated capacity, the project owner shall conduct an occupational noise survey to identify the noise hazardous areas in the facility. NOISE-6 Heavy equipment operation and noisy construction work relating to any project features shall be restricted to the times of day delineated below, unless a special permit has been issued by the City Director of Public Works.	
Solid/Hazardous Waste (Waste Management) – Construction	<ul> <li>PROJECT-SPECIFIC: Metal debris from welding/cutting activities, packing materials, electrical wiring, and empty non-hazardous chemical containers would be generated during construction. One hundred and fifteen tons of nonhazardous solid wastes generated during construction would include wood, paper, glass, and plastic waste products comprised of excess lumber, packing materials, insulation, and empty non-hazardous chemical containers</li> <li>Hazardous wastes anticipated to be generated during construction include welding materials, paint, flushing and cleaning fluids, solvents, asbestos containing materials, and lead-based paint.</li> <li>CEC staff finds that disposal of the solid wastes generated by project can occur without significantly impacting the capacity or remaining life of any of these facilities.</li> <li>CUMULATIVE: As proposed, the quantities of nonhazardous and hazardous wastes generated during construction of the project would add to the total quantities of waste generated in Los Angeles County and in the State of California. CEC staff concludes that these added waste quantities generated by the project would not result in significant cumulative waste management impacts.</li> </ul>	WASTE-1 The project owner shall provide the resume of a Registered Professional Engineer or Geologist, who shall be available for consultation during soil excavation and grading activities, to the Compliance Project Manager (CPM) for review and approval. The resume shall show experience in remedial investigation and feasibility studies. WASTE-2 If potentially contaminated soil is unearthed during excavation at either the proposed site or linear facilities as evidenced by discoloration, odor, detection by handheld instruments, or other signs, the Registered Professional Engineer or Geologist shall inspect the site, determine the need for sampling to confirm the nature and extent of contamination, and file a written report to the project owner and CPM stating the recommended course of action. WASTE-3 The project owner or	Mitigated to less than significant

Environmental Topic	Impact(s)	Mitigation	Conclusion
		construction contractor shall obtain a	
		hazardous waste generator	
		identification number from the	
		Department of Toxic Substances	
		Control prior to generating any	
		hazardous waste during construction.	
		The project owner shall obtain a	
		hazardous waste generator	
		identification number prior to	
		generating any hazardous waste during	
		operations.	
		WASTE-4 Upon becoming aware of	
		any impending waste management- related enforcement action by any	
		local, state, or federal authority, the	
		project owner shall notify the CPM of	
		any such action taken or proposed to be	
		taken against the project itself, or	
		against any waste hauler or disposal	
		facility or treatment operator with	
		which the owner contracts.	
		WASTE-5 The project owner shall	
		prepare a Construction Waste	
		Management Plan and an Operation	
		Waste Management Plan for all wastes	
		generated during construction and	
		operation of the facility, respectively,	
		and shall submit both plans to the CPM	
		for review and approval.	
		WASTE-6 The project owner shall	
		ensure that the site is properly	
		characterized and remediated if	
		necessary. The project owner shall	
		ensure a work plan is developed	
		following Department of Toxic	
		Substances Control (DTSC)	
		recommendations detailing the number	
		and location of samples of soil, soil	
		gas, and groundwater to be obtained	

Environmental Topic	Impact(s)	Mitigation	Conclusion
Solid/Hazardous Waste (Waste Management) - Operation	<b>PROJECT-SPECIFIC:</b> Nonhazardous solid wastes anticipated to be generated during operation include up to 37 tons of waste annually, comprised of maintenance wastes and office wastes. Nonrecyclable wastes would be regularly transported offsite to a solid waste disposal facility Hazardous wastes anticipated to be generated during routine project operation include waste lubricating oil, lubrication oil filters from the	and analyzed. The project owner shall assure this plan is submitted to the DTSC for review and comment, and to the CPM for review and approval. If contaminated soil is found to exist, the project owner shall assure that the City of Industry contacts DTSC for further guidance and possible oversight. In no event shall any project construction commence that involves either the movement of contaminated soil or construction on contaminated soil until the CPM has determined that all necessary remediation has been accomplished. WASTE-7 The project owner shall ensure that the cooling tower sludge is tested pursuant to Title 22, California Code of Regulations, section 66262.10 and report the findings to the CPM.	Mitigated to less than significant
	combustion turbines, spent Selective Catalytic Reduction catalyst, oily rags, cooling tower sludge, laboratory analysis waste, oil sorbents, and chemical feed area drainage. The volume of hazardous waste from the project requiring off-site disposal would be far less than CEC's staff's threshold of significance (10 percent of the existing combined capacity of the three Class I landfills) and would therefore not significantly impact the capacity or remaining life of any of these facilities.		
	<b>CUMULATIVE: :</b> As proposed, the quantities of nonhazardous and hazardous wastes generated during operation of the project would add to the total quantities of waste generated in Los Angeles County and in the State of California. CEC staff concludes that these added waste quantities generated by the project would not result in significant cumulative waste management impacts.		
Traffic and Transportation Impacts -	<b>PROJECT-SPECIFIC:</b> Staff found that traffic generated by the demolition would not reduce existing LOS to City streets below an LOS D; the designated City standard.	TRANS-1 Prior to any ground disturbance within the public right-of- way (e.g., highway, road, bicycle path,	Mitigated to less than significant

Environmental Topic	Impact(s)	Mitigation	Conclusion
Construction	The project is expected to cause a reduction in the LOS at the intersections for westbound SR-60 and South Azusa Avenue and East Gale Avenue and Bixby Drive during both morning and evening, and evening only for the intersection of the SR-60 eastbound off-ramp and South Azusa Avenue currently operates at LOS E during the evening peak hour and would remain at LOS E during peak construction The proposed 240,000 square foot (5.5 acres) parking area noted by the applicant would be of a size sufficient to address the project's peak construction workforce parking. During construction, the project's proposed primary vehicle access is at a location that provides an unobstructed viewing distance of 1,000 feet in both directions. <b>CUMULATIVE:</b> The review of potential cumulative impacts from related projects concludes that the estimated number of vehicle trips generated by them collectively could be accommodated by the City's existing road system. The estimated additional vehicle trips generated by the proposed Walnut Creek Energy Park at operation could also be accommodated by the City's existing road system (COI 2007).	pedestrian path), the project owner or its contractor(s) shall secure an encroachment permit demonstrating compliance with the applicable requirements of the City of Industry, the County of Los Angeles (if applicable), and Caltrans (if applicable) for encroachment into the public right- of-way. TRANS-3 The project owner shall prepare a construction traffic control and implementation plan for the project and its associated facilities. The project owner shall consult with the City of Industry Engineering and Planning Departments, the Los Angeles County Department of Public Works (if applicable), and Caltrans (if applicable) in the preparation of the traffic control and implementation plan. The project owner shall provide a copy of the City of Industry Engineering and Planning Departments, the Los Angeles County Department of Public Works (if applicable), and Caltrans (if applicable) in the preparation of the traffic control and implementation plan. The project owner shall provide a copy of the City of Industry Engineering and Planning Departments, the Los Angeles County Department of Public Works, and Caltrans written comments and a copy of the traffic control and implementation plan to the CPM for review and approval. TRANS-4 The project owner shall repair to original or near original condition affected public rights-of-way (e.g., highway, road, bicycle path, pedestrian path) that have been damaged due to construction activities conducted for the project and its associated facilities.	

Environmental Topic	Impact(s)	Mitigation	Conclusion
Traffic and Transportation Impacts - Operation	<ul> <li><b>PROJECT-SPECIFIC:</b> The estimated project employee trips would result in a tenfold reduction in total trip generation when compared to employee trips generated by the current warehouse operation. Therefore, trips by the project operation employees would not result in a significant adverse impact to traffic and transportation.</li> <li>Truck trips would not significantly impact the existing LOS for area roads. The very limited occurrence (frequency and duration) of ground level fogging created by the project's cooling towers would generate a less than significant impairment of visibility to motorists on nearby public roads and highways.</li> <li>During operation, the project's proposed primary vehicle access is at a location that provides an unobstructed viewing distance of 1,000 feet in both directions.</li> <li><b>CUMULATIVE:</b> The review of potential cumulative impacts from related projects concludes that the estimated number of vehicle trips generated by them collectively could be accommodated by the City's existing road system. The estimated additional vehicle trips generated by the City's existing road system (COI 2007).</li> </ul>	TRANS-2 The project owner shall comply with the applicable parking standards of the City of Industry, and the County of Los Angeles (if applicable). The project owner shall prepare and submit to the CPM for approval a parking plan(s) for the construction and operation phases of the project in consultation with the City of Industry Engineering and Planning Departments, the Los Angeles County Department of Public Works (if applicable), and the Los Angeles County Fire Department (if applicable). TRANS-5 Prior to the start of commercial operation the project owner shall submit written notification to the Los Angeles County Sheriff's Department Aero Bureau informing them of the start of commercial operation date for the power plant, and advising them that potential turbulence caused by thermal plumes emitted from the power plant's cooling towers and combustion turbine generator stacks may adversely affect aircraft flying directly over the power plant below an elevation of 500 feet above ground level.	Less than significant